

Bid Results

Item	Description	Material Quantity	Price Per	Sierra Single Ply		Roofing Plus
				Year 1	Year 1 with Multipliers	Non Responsive
A	DEMOLITION: ROOF SHINGLES (price includes demolition and disposal of roof shingles, flashings, roof jacks and roofing paper):					
1	Tear off and disposal of one (1) layer of asphalt roof shingles	Per project	Square Feet	1.25	12.5	
2	Tear off and disposal of two (2) layers of asphalt roof shingles	Per project	Square Feet	1.65	11.55	
3	Tear off and disposal of three (3) layers of asphalt roof shingles	Per project	Square Feet	2	4	
B	DEMOLITION OF: FASCIA, RAFTERS, ROOF SHEATHING, GUTTERS, ETC.:					
4	Demolish and dispose of barge rafter/fascia board (up to and including 2x12)	Per project	Linear Feet	1	6	
5	Demolish and dispose of rafter tails or outriggers	Per project	Each	2	6	
6	Demolish and dispose of frieze blocks (up to and including 2x8)	Per project	Each	0.5	0.5	
7	Demolish and dispose of soil/exhaust/heater vent	Per project	Each	0.5	0.5	
8	Demolish and dispose of 1/2 inch roof sheathing	Per project	Square Feet	1	15	
9	Demolish and dispose of 1X roof sheathing (up to and including 1X8)	Per project	Linear Feet	0.5	3	
10	Demolish and dispose of fascia gutter with rain water leaders (and gutter guards if applicable)	Per project	Linear Feet	2	20	
C	INSTALLATION: ASPHALT ROOF SHINGLES (unit price shall include roofing materials and the following roof accessories for typical installation: Asphalt shingles as specified in individual Project scope, hip and ridge shingles as apply to Project, Mtl. drip edge, 30 lb. asphalt felt, new roof jacks, 18 in. sht. mtl. valley flashing):					
11	Install asphalt roof shingles	1 to 500 sq ft	Square Feet	5.95	89.25	
12	Install asphalt roof shingles	501 sq ft & higher	Square Feet	5.5	110	
13	Install "Cool Series" asphalt roof shingles	1 to 500 sq ft	Square Feet	5.95	89.25	
14	Install "Cool Series" asphalt roof shingles	501 sq ft & higher	Square Feet	5.5	110	
D	INSTALLATION: BARGE RAFTER/FASCIA BOARD/RAFTER TAILS (price includes materials, preparation, and complete installation):					
15	Install 1 inch X 6 inch barge rafter/fascia board	Per project	Linear Feet	4	8	
16	Install 1 inch X 8 inch barge rafter/fascia board	Per project	Linear Feet	4.5	9	
17	Install 2 inch X 6 inch barge rafter/fascia board	Per project	Linear Feet	6.5	52	

Bid Results

Item	Description	Material Quantity	Price Per	Sierra Single Ply		Roofing Plus
				Year 1	Year 1 with Multipliers	Non Responsive
18	Install 2 inch X 8 inch barge rafter/fascia board	Per project	Linear Feet	9.5	76	
19	Install 2 inch X 10 inch barge rafter/fascia board	Per project	Linear Feet	12	48	
20	Install 2x4 or 2x6 rafter tails (see detail)	Per project	Each	7	42	
21	Install 2x4 or 2x6 frieze blocks at eaves	Per project	Each	2	10	
22	Install 2x4 or 2x6 outriggers (for barge rafter support - see detail)	Per project	Each	14	70	
E	INSTALLATION: SHEATHING (price includes materials, preparation, and complete installation):					
23	Install 1/2 inch CDX plywood or OSB sheathing	1 to 64 square ft	Square Feet	3	60	
24	Install 1/2 inch CDX plywood or OSB sheathing	65 sq ft & higher	Square Feet	2.5	62.5	
25	Install 1/2 inch ACX plywood sheathing at eaves	Per project	Square Feet	3	30	
26	Install 1/2 inch plywood sheathing (eaves)	Per project	Square Feet	3	30	
					0	
F	INSTALLATION: GUTTERS & DOWNSPOUTS, GUTTER GUARD, VENTS, ETC. (price includes materials, preparation, and complete installation):					
27	Install rain water leaders	Per project	Linear Feet	10	20	
28	Install 5" galvanized steel fascia gutters	Per project	Linear Feet	11.5	34.5	
29	Install 7" galvanized steel fascia gutters	Per project	Linear Feet	12	60	
30	Install 5" seamless aluminum fascia gutters	Per project	Linear Feet	12	60	
31	Install 7" seamless aluminum fascia gutters	Per project	Linear Feet	14	112	
32	Install ogee gutters (assume 5" size)	Per project	Linear Feet	12	96	
33	Install gutter guard	Per project	Linear Feet	2.5	7.5	
34	Install 2 or 3 inch dia. Roof jack	Per project	Each	10	50	
35	Install 4 or 5 inch dia. Roof jack	Per project	Each	30	90	
36	Install 23"x32" low-profile attic vent	Per project	Each	50	300	
37	Install ridge vent	Per project	Linear Feet	5	40	
38	Install step shingles	Per project	Linear Feet	1	6	

Bid Results

Item	Description	Material Quantity	Price Per	Sierra Single Ply		Roofing Plus
				Year 1	Year 1 with Multipliers	Non Responsive
39	Install alumninum step flashing	Per project	Linear Feet	1.5	9	

Total of
Year 1 \$1,860.05